

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

SEP 9 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name William A. Cecil

Complete Address: 722 Union Center Bldg., Wichita, Kansas

Lease Name Gress-Winter Well No. # 1

Location SE NW Sec. 8 Twp. 31 Rge. 12 (E) (W) W

County Barber Total Depth 3757

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 1:30PM Day 8th Month Sept. Year 1964

The Above well was plugged as follows:

250' of 8 5/8" surface pipe, cemented with 175 sacks. 3757' of 4 1/2" long
string, top of cement 3260'. Top perforation 3677'. Bottom of the hole
was sanded to 3660', and cemented with 3 sacks. Hole was bailed down to
a fluid level of 245'. Bridge plug was set on fluid at 245', and 10' of
rock bridge, cemented with 25 sacks. Hole was filled with mud to 40',
and 10' of rock bridge, cemented with 10 sacks to the base of the cellar.
3100' of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 9/9/64

INV. NO. 9786-U