

14
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

FEB 21 1966

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name K & E Drilling, Inc.

Complete Address: 719 Union Center Bldg., Wichita, Kansas

Lease Name Gress "B" Well No. # 1

Location C NE SE Sec. 18 Twp. 31 Rge. 12 (E) (W) W

County Barber Total Depth 3777'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: K & E Drilling, Inc.

Address: 719 Union Center Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 7:00 AM Day 18th Month Feb. Year 1966

The Above well was plugged as follows:

264' of 8 5/8" surface pipe, cement circulated with 175 sacks. Hole
was filled with drilling mud to 260', 1st cementing plug, bridged
solid with hulls on fluid at 260', and cemented with 25 sacks. Hole
was filled with drilling mud to 40', 2nd cementing plug, bridged
solid with hulls on fluid at 40', and cemented with 10 sacks to the
base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2/21/66

INV. NO. 2749-U