

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL H. OGDEN, Director

GEORGE DOCKING Governor
MARION BEATTY Chairman
HARRY G. WILES Commissioner
RICHARD C. BYRD Commissioner
RAYMOND B. HARVEY Secretary
CLYDE E. MILLIGAN Counsel

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date October 20, 1958, authorized the following plugging operation:

Operator's Full Name: Pickerell Drilling Co.

Complete Address: 705 Fourth National Bank Bldg., Wichita, Ka

Lease Name: McKeever "B" Well No. 1

Location: CSW SE Sec. 35 Twp. 31 Rge. 10 (E) (W) X

County: Barber Total Depth: 4540

Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

260' of 8 5/8" surface casing circulated with cement. Topperf. 4450'. Pumped 10 sack cement on bottom from 4450'. Fill hole to 250' with heavy jell mud. Set rock bridge from 250'. Place 20 sack cement top rock bridge. Heavy mud to 35'. Rock Bridge from 35'. Place cement from rock bridge to base of cellar.

Very truly yours,

Signed: [Signature] Conservation Division Agent

RECEIVED STATE CORPORATION COMMISSION

NOV 7 1958

CONSERVATION DIVISION Wichita, Kansas

CPB