

40
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 2 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Siuox Petroleum

Complete Address: 104 East Kansas, Medicine Lodge, Kansas

Lease Name McReynolds Well No. # 1

Location C NW NW Sec. 30 Twp. 31 Rge. 10 (E) (W) W

County Barber Total Depth 4525'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Clarke Corporation, Inc.

Address: Chapin Bldg., Medicine Lodge, Kansas License No. 583

Operation Completed: Hour 11:15AM Day 29th Month August Year 1966

The Above well was plugged as follows:

250' of 8 5/8" surface pipe, cemented with 200 sacks. 4525' of 4 1/2" long
string, cemented with 100 sacks. Top perferation 4512'. Bottom of the
hole was sanded to 4500', and cemented with 3 sacks, through the dump
bailer. 3683' of 4 1/2" long string was recovered from the hole. Fluid in
the hole was bailed down to 240', bridge plug and rock bridge from 240'
to 230', and cemented with 25 sacks. Hole was filled with mud to 40',
rock bridge from 40' to 30', and cemented with 10 sacks to the base of
the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/2/66

INV. NO. 3862-11

Signed: Audie Elving
Well Plugging Supervisor