

R
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 7 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Sierra Petroleum Company, Inc.

Complete Address: 1015 Wichita Plaza Bldg., Wichita, Kansas

Lease Name McReynolds Well No. # 1

Location C SW SE Sec. 30 Twp. 31 Rge. 10 (E) (W) W

County Barber Total Depth 4626'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Sierra Petroleum Company, Inc.

Address: 1015 Wichita Plaza Bldg., Wichita, Kansas License No.

Operation Completed: Hour 11:30PM Day 4th Month July Year 1965

The Above well was plugged as follows:

210' of 8 5/8" surface pipe, cement circulated with 185 sacks. Hole
was filled with drilling mud to 210', 1st cementing plug, bridged
solid with dry cement and hulls on fluid at 210', and cemented with
25 sacks. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with dry cement and hulls on fluid at 40', and
cemented with 10 sacks to the base of the cellar. Rat hole bridged
and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/7/65

INV. NO. 1428-W

Signed: Archie Elving
Well Plugging Supervisor