

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 24 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Sierra Petroleum Company, Inc.

Complete Address: 1015 Wichita Plaza, Wichita, Kansas

Lease Name McReynolds Well No. # 1

Location App. SW SW NW Sec. 32 Twp. 31 Rge. 10 (E) (W) W

County Barber Total Depth 3700'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: This hole was a wash down

Plugging Contractor: Hellar Drilling Company, Inc.

Address: 1014 Union Center, Wichita, Kansas License No.

Operation Completed: Hour 12:30AM Day 23rd Month Sept. Year 1965

The Above well was plugged as follows:

247' of 8 5/8" surface pipe, cement circulated. Hole was filled with
drilling mud to 240', 1st cementing plug, bridged solid with dry cement
and hulls on fluid at 240', and cemented with 30 sacks. Hole was filled
with drilling mud to 40', 2nd cementing plug, bridged solid with dry
cement and hulls on fluid at 40', and cemented with 10 sacks to the
base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 9/27/65

INV. NO. 1855-W