

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 007 - 10800 - 00 - 00 (of this well)

Operator's Full Name Texas Oil & Gas Corp.

Complete Address 200 W. Douglas, Suite 300, Wichita, Ks. 67202

Lease Name Gress "B" Well No. 1

Location C SW SE Sec. 20 Twp. 31s Rge. 12 (E) (W) X

County Barber Total Depth 4360

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Clarke Oilfield Service.

Address 107 W. Fowler, Medicine Lodge, Ks. 67104 License No. 583

Operation Completed: Hour 11:30 Am. Day 1 Month 2 Year 1980

The above well was plugged as follows:

325' 8 5/8" casing w/225 sax cement. 2 7/8" casing set at 4344' w/200
sax cement. Plug back to 4270'-Top pref., at 4216'-Allied mixed &
pumped 25 sax common cement in 2 7/8" casing to 3730'-Pull 3000"
casing. Allied mixed & pumped 5 sax hulls-20 sax gel-100 sax 50/50
posmix cement w/4% gel to top of casing. Shut in w/400# pressure.

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2-5-80

INV. NO. 1456-w

Signed: [Signature] FEB - 4 1980
Well Plugging Supervisor
CONSERVATION DIVISION
Wichita, Kansas