

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 8 1966

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name E. K. Edmiston

Complete Address: 425 First National Bank Bldg., Wichita, Kansas

Lease Name Massoni Well No. # 1

Location C SE NE Sec. 24 Twp. 30 Rge. 11 (E) (W) W

County Barber Total Depth 4800'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Edmiston Drilling Company, Inc.

Address: 425 First National Bank Bldg., Wichita, Ks. License No. _____

Operation Completed: Hour 11:00AM Day 5th Month August Year 1966

The Above well was plugged as follows:

.244' of 8 5/8" surface pipe, cement circulated with 175 sacks. Hole
was filled with drilling mud to 240', 1st cementing plug, bridged with
2 sacks of dry cement and 1/2 sack of hulls on fluid at 240', and cemented
with 23 sacks. Hole was filled with drilling mud to 40', 2st cementing
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid
at 40', and cemented with 9 sacks to the base of the cellar. Rat hole
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 8-8-66

INV. NO. 3710-W