

**KANSAS**  
**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

**RECEIVED**  
STATE CORPORATION COMMISSION

APR 12 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Rains & Williamson Oil Company

Complete Address: 1425 Wichita Plaza, Wichita, Kansas

Lease Name Laverentz Well No. # 1

Location C NE NW Sec. 21 Twp. 30 Rge. 11 (E) (W) W

County Barber Total Depth 4850'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Rains & Williamson Oil Company

Address: 1425 Wichita Plaza, Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 5:00AM Day 10th Month April Year 1965

The Above well was plugged as follows:

262' of 8 5/8" surface pipe, cement circulated with 200 sacks. Fluid  
level in the hole was at 180'. 1st cementing plug and 1/2 sack of hulls  
was pushed in fluid to 250', and cemented with 25 sacks, through the  
drill pipe. Hole was filled with mud to 40', 2nd cementing plug,  
bridged solid with hulls on fluid at 40', and cemented with 10 sacks  
to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Archie Elving  
Well Plugging Supervisor

DATE 4/12/65  
INV. NO. 960-W