

KANSAS

FORM CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

J. Lewis Breck  
Administrator  
245 North Water  
Wichita, Ks. 67202

API Number 15 - 007-00824-00-01 (of this well)

Operator's Full Name Rupe Oil Co.

Complete Address Box 2273-Wichita, Ks. 67201

Lease Name Amy Rolf Well No. 1

Location NW NW SW Sec. 5 Twp. 30s Rge. 11 (E) (W) W

County Barber Total Depth 4467

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D&A     

Other well as hereafter indicated     

Plugging Contractor Clarke Corp.

Address 107 W. Fowler, Medicine Lodge, Ks. 67101 License No. 583

Operation Completed: Hour 4:15 PM Day 14 Month 10 Year 1980

The Above well was plugged as follows:

220' 8 5/8" casing. 4 1/2" casing set at 3783'-Plug back to 3012'-Top  
preformation 2760'-Allied mixed & pumped in 4 1/2" casing 35 sax common  
cement to 2480'-Pull 2400' casing-Allied mixed & pumped in 8 5/8"  
casing 8 sax hulls-25 sax gel-125 sax 50/50 posmix cement w/4% gel  
& 3% cc to top of casing. Shut in w/200# pressure.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 16 1980  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 10-17-80

INV. NO. 3376-W