

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 3 1966

CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasOperator's Full Name E. K. EdmistonComplete Address: 425 First National Bank Bldg., Wichita, KansasLease Name Ferrel Well No. # 1Location C NW NE Sec. 15 Twp. 30 Rge. 11 (E) (W) WCounty Barber Total Depth 4865'Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: Plugging Contractor: E. K. Edmiston Drilling CompanyAddress: 425 First National Bank Bldg., Wichita, Ks. License No. Operation Completed: Hour 2:30AM Day 31st Month Dec. Year 1966

The Above well was plugged as follows:

245' of 8 5/8" surface pipe, cement circulated with 200 sacks. Fluid level in the hole was at 150'. 1st cementing plug and 1/2 sack of hulls was pushed in fluid to 240', and cemented with 25 sacks, through the drill pipe. Hole was filled with drilling mud to 40', 2nd cementing plug, bridged with 1/2 sack of hulls on fluid at 40', and cemented with 10 sacks to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 1/4/67INV. NO. 4534-u