

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 11 1968
CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasIntent to Drill,
filed December 26, 1967.

Operator's Full Name Parley Oil Company

Complete Address: P. O. Box 14371, Oklahoma City, Oklahoma

Lease Name Sapphire Well No. # 1

Location C NW NW Sec. 15 Twp. 35 Rge. 6 (E) W

County Harper Total Depth 4070'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Gabbert-Jones, Inc.

Address: 830 Sutton Place, Wichita, Kansas License No. _____

Operation Completed: Hour 10:00PM Day 6th Month January Year 1968

The Above well was plugged as follows:

247' of 8 5/8" surface pipe, cement circulated with 225 sacks. Hole was
filled with drilling mud to 240', 1st cementing plug, bridged with 1 sacks
of dry cement and 1 sack of hulls on fluid at 240', and cemented with 24 sack
with cement from 230' to 155'. Hole was filled with drilling mud to 40', 2nd
cementing plug, bridged with 1 sack of dry cement and 1 sack of hulls on
fluid at 40', and cemented with 9 sacks to the base of the cellar. Rat hole
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 1/11/68
INV. NO. 7092-WSigned: Archie Elving
Well Plugging Supervisor