

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUN 29 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska

Lease Name M. B. Hull Well No. # 1

Location SW NE NW Sec. 20 Twp. 34 Rge. 13 (E) (W) W

County Barber Total Depth 4175

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Leben Drilling Inc.

Address: 912 Central Bldg., Wichita, Kansas License No.     

Operation Completed: Hour 10:30PM Day 27th Month June Year 1964

The Above well was plugged as follows:

437' of 8 5/8" surface pipe, cemented with 275 sacks. Fluid level in  
the hole was at 210'. Plug was set on fluid at 210', bridged solid  
hulls; and cemented with 25 sacks. Hole was filled with drilling mud  
to 40', 2nd cementing plug, bridged solid with hulls at 40', and cem-  
ented with 10 sacks to base of the cellar. Rat hole bridged and cement-  
ed with 2 sacks.

This cementing was done by Halliburton Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 6/29/64

INV. NO. 9344-4

CP3