

Form CP-3
Rev. 6-26-62

4
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUN 8 1964
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Solar Oil Company

Complete Address: 1117 Union National Bldg., Wichita, Kansas

Lease Name Stone Well No. # 1

Location C NW NE Sec. 22 Twp. 31 Rge. 10 (E) (W) W

County Barber Total Depth 4965

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Sierra Petroleum Co., Inc.

Address: 1015 Wichita Plaza, Wichita, Kansas License No.

Operation Completed: Hour 8:00PM Day 4th Month June Year 1964

The Above well was plugged as follows:

250' of 8 5/8" surface pipe, cemented with 200 sacks. Hole was filled
with drilling mud to 260', 1st cementing plug, bridged solid with wood
and hulls, on fluid at 260', and cemented with 25 sacks, bringing the
top of the cement to 160' in the surface pipe. Hole was filled with
drilling mud to 40', 2nd cementing plug, bridged solid with hulls, on
fluid at 40', and cemented with 10 sacks to base of the cellar.
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 6/9/64
INV. NO. 9280-4