

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasRECEIVED
STATE CORPORATION COMMISSIONDEC - 6 1965
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Beardmore Drilling Company

Complete Address: 700 One Twenty Bldg., Wichita, Kansas

Lease Name Rankin Well No. # 1

Location C SW SW Sec. 13 Twp. 31 Rge. 10 (E) (W) W

County Barber Total Depth 3825'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: This hole was a wash down.

Plugging Contractor: Walters Drilling Company

Address: 510 Orpheum Bldg., Wichita, Kansas License No.

Operation Completed: Hour 3:15 AM Day 3rd Month Dec. Year 1965

The Above well was plugged as follows:

257' of 10 3/4" surface pipe, cement circulated. Hole was filledwith drilling mud to 250', 1st cementing plug, bridged solid withdry cement and hulls on fluid at 250', and cemented with 30 sacks.Hole was filled with drilling mud to 40', 2nd cementing plug, bridgedsolid with dry cement and hulls on fluid at 40', and cemented with15 sacks to the base of the cellar. Rat hole bridged and cementedwith 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 12/4/65INV. NO. 2351-W