

40  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAY 14 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name K & E Drilling Co. - W. J. Coppinger

Complete Address: 719 Union Center, Wichita, Kansas

Lease Name Inslee Well No. # 1

Location C NW SW Sec. 18 Twp. 31 Rge. 10 (E) (W)W

County Barber Total Depth 4556

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: K & E Drilling Co.

Address: 719 Union Center, Wichita, Kansas License No.     

Operation Completed: Hour 3:00AM Day 12th Month May Year 1963

The Above well was plugged as follows:

232' of 8 5/8" surface pipe, cement circulated with 175 sacks. Hole was  
filled with mud to 180', 1st cementing plug. 1/4 sack hulls, cemented with  
20 sacks. Hole was filled to 40' with mud, 2nd cementing plug, 1/4 sack  
hulls, cemented with 10 sacks to base cellar.  
Rat hole was bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

DATE 5/14/63  
INV. NO. 7096-W

Signed: Archie Elving  
Well Plugging Supervisor