

KANSAS

FORM CP-3  
Rev. 10-8-81

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15- - ✓

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Rupe Oil Co., Inc.

Complete Address Box 2273, 434 Ohio, Wichita, Kansas 67201

Lease Name Shaw Well No. 1

Location C of N/2 SE/4 Sec. 6 Twp. 30 Rge. 12W (East)(West)

County Barber Total Depth 3036'

Abandoned Oil Well      Gas Well XX Input Well      SWD Well      D&A     

Other well as hereinafter indicated     

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698, Great Bend, Kansas 67530 License No.     

Operation Completed: Hour: 12:15 PM Day: 28 Month: 12 Year: 19 81

Plugging Operations attended by Agent?: All XX Part      None     

The above well was plugged as follows:

286' of 8 5/8" SP W/225 sks

4 1/2" csg. set @ 2875' W/150 sks Plug Back to 2848'

Top Perf 2788' to 2790' Sand Back to 2750' & W/4 sks

Pumped 15 gel 6 hulls 10 gel, released plug and displaced W/150 sks

common cement, 2% gel 3% C.C. Rec. 2100' of 4 1/2" csg. SIP 200#

Cemented by Howco

RECEIVED  
STATE CORPORATION COMMISSION

JAN - 5 1982

I hereby certify that the above plugging instructions were given as herein stated.

Signed: *M. T. Deane*  
Conservation Division Agent

1-18-82  
8871-W