

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Intent to Drill,  
filed August 29, 1967.

Operator's Full Name W. C. Payne

Complete Address: 800 United Founders Tower, Oklahoma City, Oklahoma

Lease Name Gibson Well No. # 1

Location C NE SW Sec. 3 Twp. 30 Rge. 12 (E) (W) W

County Barber Total Depth 5707' 4707'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Garvey Drilling Company

Address: R. R. # 2, Great Bend, Kansas 67530 License No.     

Operation Completed: Hour 7:00PM Day 11th Month Sept. Year 1967

The Above well was plugged as follows:

378' of 8 5/8" surface pipe, cement circulated with 300 sacks. Hole was  
filled with drilling mud to 300', 1st cementing plug, bridged with 1/2 sack  
of hulls on fluid at 300', and cemented with 20 sacks, with cement from 290'  
to 230'. Hole was filled with drilling mud to 35', 2nd cementing plug bridged  
with 1/2 sack of hulls on fluid at 35', and cemented with 8 sacks, with cement  
from 25' to the base of the cellar. Rat and mouse holes bridged and cemented  
with 4 sacks.

I hereby certify that the above well was plugged as herein stated.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 15 1967

Signed: Archie Elving  
Well Plugging Supervisor

INVOICED

DATE 9/15/67  
INV. NO. 6332-W

CONSERVATION DIVISION  
Wichita, Kansas