

W
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 9 1963

7-9-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Aylward Drilling Co.

Complete Address: 909 1st National Bank Bldg., Wichita, Kansas

Lease Name Whelan Well No. # 2

Location C NW SW Sec. 29 Twp. 31 Rge. 11 (E) (W) W

County Barber Total Depth 4358

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 304, Chase, Kansas License No. 436

Operation Completed: Hour 3:00PM Day 3rd Month July Year 1963

The Above well was plugged as follows:

125' of 8 5/8" surface pipe, cement circulated. 4325' of 5 1/2" long string.
Sanded to 4315', cemented with 5 sacks. Hole was bailed down and plug
was set at 190', 10' rock bridge, cemented with 25 sacks. Hole was filled
with mud to 40', 10' rock bridge, cemented with 10 sacks to base cellar.
2935' of 5 1/2" long string recovered from hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/9/63

INV. NO. 7284-W

Signed: Audie Elving
Well Plugging Supervisor