

15-007-10031-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 17 1963

7-17-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Aylward Drilling Co.

Complete Address: 909 1st National Bank Bldg., Wichita, Kansas

Lease Name Whelan Well No. # 1

Location SW SW SW Sec. 29 Twp. 31 Rge. 11 (E) (W) W

County Barber Total Depth 4316

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 304, Chase, Kansas License No. 436

Operation Completed: Hour 9:00AM Day 12th Month July Year 1963

The Above well was plugged as follows:

142' of 13 3/8" surface pipe, cement circulated. 4304' of 7" long string,
cement unknown. Sanded to 4290', cemented with 6 sacks. Fluid would not
bail down in hole. Plug was set at 235', and 33 sacks cement was mixed and
put on plug through dump bailer and let set over night, Next morning cement
level was 120' in surface pipe, and fluid was bailed down, 11 sacks cement
was added to plug. Hole was filled with mud to 40', 10' rock bridge, cement-
ed with 21 sacks to base cellar.

3237' of 7" long string recovered from hole.

I hereby certify that the above well was plugged as herein stated.

NOTICED

DATE 7-17-63

INV. NO. 7422-W

Signed: Archie Elving
Well Plugging Supervisor