

KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 11 1959  
8-11-59  
CONSERVATION DIVISION  
Wichita, Kansas

File No. 40-44 County: Barber  
Location: SW SW NE Sec. 39 Twp. 31 Rge. 11 (E) (W) ☒  
Name of Field: \_\_\_\_\_ Total Depth: 4485

I have this date completed supervision of plugging of:

Lease Name: Whelan "C" Well No. 1Operator's Full Name: Lario Oil & Gas Co.Complete Address: 301 So. Market, Wichita, Kans.Plugging Contractor: G. Lenn & Smith Casing Pulling Co.Address: \_\_\_\_\_ License No. 396Oil Well ☒ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No ☒

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 5 PM Day 27 Month July Year 1959

The above well was plugged as follows:

134' of 8" surface casing. Top per 4364. Hole was  
sanded to 4345 and 55 cent dumped with dump  
bailer. 3983' of 5" protection pipe pulled. Hole was  
filled to 127' with heavy mud. Rock bridge set  
from 127' to 123. 205 cent poured top bridge.  
Heavy mud to 30. Rock bridge from 30 to 25.  
Cement poured from bridge to base of collar.

Signed: W. L. Karp  
Conservation Division AgentReviewed: J. Lewis Brock  
Field Supervisor

Remarks:

PLUGGING  
FILE SEC. 29 31 R. 11  
BOOK PAGE 40 LINE 44