

3-15-88

2 050665

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 077-20,790-00-00  
SEC. 22, T 32, S, R 8 WX  
660 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171  
Operator: TXO Production Corporation  
Name & Address: 155 N. Market, Suite 1000  
Wichita, KS 67202

Lease Name Robinson Well # G#2  
County Harper 128.38  
Well Total Depth 3950 PBDT 2908 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 271

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers License Number 4635  
Address Great Bend, KS 67530

Company to plug at: Hour: 8:00am Day: 13 Month: 3 Year: 19 88

Plugging proposal received from Richard  
(company name) TXO Production Corporation (phone) \_\_\_\_\_

were: 4 1/2" set @3949 w/225 sxs cement. Perf @3668-76, 3650-62, 3637-42, 3620-27.  
Shoot and pull pipe. Plug perms w/10 sxs cement. Squeeze 8 5/8" with  
4 hulls, 15 gel, 115 sxs cement.

Plugging Proposal Received by Don Thompson (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 9:30am Day: 15 Month: 3 Year: 1988

ACTUAL PLUGGING REPORT Pumped 1 sxs hulls, 20 sxs cement down 4 1/2" to bottom over perf.  
Shot and pulled 2400' of 4 1/2" casing. Squeezed 8 5/8 w/4 sxs hulls, 15 sxs gel  
and 115 sxs 60/40 poz. Max 850# Shut in 350#

RECEIVED  
STATE CORPORATION COMMISSION

MAR 21 1988

Remarks: B. J. Titan 60/40 poz  
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED I reserve this plugging.

Signed Glenn S. Ward pd (TECHNICIAN)

DATE 3-21-88  
INV. NO. 20146