

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-21387-00-00  
Spot: N2NE Sec/Twnshp/Rge: 5-34S-8W  
660 feet from N Section Line, 1320 feet from E Section Line  
Lease/Unit Name: ZIMMERMAN C Well Number: 1  
County: HARPER Total Vertical Depth: 4700 feet

Operator License No.: 30535  
Op Name: HARTMAN OIL CO., INC.  
Address: 12950 E. 13TH  
WICHITA, KS 67230

Production Casing Size: 5.5 feet: 4698 175 SX CMT  
Surface Casing Size: 8.625 feet: 263 250 SX CMT

*75*  
*\$152*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/25/2003 1:45 PM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: EDWARD S. NEMNICH Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: Perfs 4402' - 4578'; Sand to 4330' & 5 sacks; 35 sacks @ 1250'; 35 sacks @ 850'; circulate 310' - 0'.

RECEIVED  
KCC DISTRICT #2  
SEP 29 2003  
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI Witness Type: Plugging Operations Partially Witnessed  
Date/Time Plugging Completed: 09/25/2003 2:45 PM KCC Agent: STEVE VANGIESON

**Actual Plugging Report:**

The perfs were covered with sand to 4330' and capped with 5 sacks cement. The casing was recovered from 2950' and pulled to 1250' where 35 sacks of cement was spotted. Pulled casing to 850' and spotted 35 sacks cement. Pulled casing to 310' and circulated cement to surface.


RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 02 2003  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENT 60/40 4% GEL

Plugged through: CSG

District: 02

Signed \_\_\_\_\_



(TECHNICIAN)

**INVOICED**

DATE 10-2-03

INV. NO. 2004060564