

2 040483

1-6

153 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-077-20372-00-00

NE NE, SEC. 34, T 33 S, R 7 W/XX

4620 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5038

Lease Name Mollohan Well # A-1

Operator: Robinson Oil Co.

County Harper 163.74

Name & Address 300 W. Douglas #420

Well Total Depth 5038' feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8-5/8 feet 244

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from Dallas

(company name) Kelso Casing (phone) \_\_\_\_\_

were: 4-1/2" 4753' PBD 4692.5' Perfed 4558-62' - 4562-66'

Sand to 4000' & 4 sx - plug at 1000', 750', 260 - 0

RECEIVED  
STATE CORPORATION COMMISSION

MAR 24 1989

CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Steve Van Gieson  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:00 Day: 6 Month: 1 Year: 19 89

ACTUAL PLUGGING REPORT The perfs were sanded to 4000' & capped with 4 sx cement - casing was shot off at 3759' - casing was pulled to 981' where 25 sx cement was spotted - casing was pulled to 721' and 25 sx cmt was spotted - casing was pulled to 260' and cmt was circ to surface with 90 sx.

Remarks: B. J. Titan #512853 60/40 poz 2% gel  
(If additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

Signed [Signature]  
(TECHNICIAN)

DATE 3-30-89

INV. NO. 24309