

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-20209-00-01
Spot: SENW Sec/Twnshp/Rge: 31-33S-7W
3165 feet from S Section Line, 3190 feet from E Section Line
Lease/Unit Name: TRUBY A OWWO Well Number: 1-31
County: HARPER Total Vertical Depth: 4720 feet

Operator License No.: 5003 Conductor Pipe: Size _____ feet: 8 153.40
Op Name: MCCOY PETROLEUM CORPORATION Surface Casing: Size 8.625 feet: 268
Address: 453 S. WEBB RD. STE 310 PO BOX 78020 Production: Size 4.5 feet: 4714 175 SX CMT
WICHITA, KS 67278 Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/25/2002 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: _____

Proposed Plugging Method: Perfs 4652'-67'. Sand to 4600' and 4sxs. 35sxs-1500'. 35sxs-1000'. Circulate to 320'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 07/25/2002 11:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perfs were sanded back to 4587' and capped w/4sxs of cement. The casing was recovered from 3407' and pulled to 1500' where 35sxs of cement was spotted. Pulled to 1000' spotted 35sxs. Pulled to 320' and circulated cement to surface. Pulled remaining casing and topped off cement.

RECEIVED
KCC DISTRICT #2
AUG 02 2002
WICHITA, KS

Remarks: ALLIED CEMENT 60/40 POZ., 4% GEL

Plugged through: CSG

District: 02

Signed [Signature]
(TECHNICIAN)

INVOICED
DATE 8-5-02
TEL. NO. 2003060165