

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

9-18

API NUMBER: 15-077-20,140-00-01

NE NW SW, SECTION 28 TOWNSHIP 33 RANGE 8W

OPERATOR LICENSE # 31191 2310 FEET FROM S SECTION LINE
OPERATOR R & B OIL & GAS INC 4290 FEET FROM E SECTION LINE
NAME & P.O. BOX 195
ADDRESS ATTICA, KS 67009

LEASE NAME: KASTENS A OWVO #1
COUNTY: HARPER 150.48
WELL TOTAL DEPTH: 4630' PBTD 4150'
PIPE: 4 1/2" @ 4628'
SURFACE CASING: 8 5/8" @ 261'

ABANDONED OIL WELL _____ GAS WELL X INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: SHAWNEE WELL SERVICE

ADDRESS: ATTICA, KS LICENSE: 30346

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: JEFF CAPPS

COMPANY NAME: SHAWNEE WELL SERVICE PHONE: _____

WERE: PERFS 4119-20'

SAND TO 4060'

35 SACKS AT 1350'

35 SACKS AT 900'

CIRCULATE 300' TO SURF

PLUGGING PROPOSAL RECEIVED BY: _____

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (X) NONE (_____)

COMPLETED: HOUR: 18:30 DAY: 18 MONTH: 9 YEAR: 1997

ACTUAL PLUGGING REPORT: THE PERFS WERE COVERED WITH SAND TO 4060' AND CAPPED WITH 4 SACKS OF CEMENT. THE CASING WAS PULLED FROM 3445' TO 1360' WHERE 35 SACKS OF CEMENT WAS SPOTTED. CASING WAS PULLED TO 895' WHERE 35 SACKS OF CEMENT WAS SPOTTED. CASING WAS PULLED TO 305' WHERE CEMENT WAS CIRCULATED TO SURFACE.

RECEIVED
KANSAS CORPORATION COMMISSION

REMARKS: 60/40 POZ 4% GEL ALLIED CEMENT NOV 18 1997

I DID OBSERVE THIS PLUGGING.
CONSERVATION DIVISION
WICHITA, KS

[Signature]
STEVE VAN GIESON

INVOICED
NOV 20 1997

DATE _____
INV. NO. 49546