

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

9-19

API NUMBER: 15-077-20,815-00-00

SE SW, SECTION 20 TOWNSHIP 33 RANGE 8W

OPERATOR LICENSE # 3288 660 FEET FROM S SECTION LINE  
OPERATOR JODY OIL & GAS CORPORATION 1980 FEET FROM SECTION LINE  
NAME & P.O. BOX 422  
ADDRESS ATTICA, KS 67009

LEASE NAME: MCKINNEY #1  
COUNTY: HARPER 146.77  
WELL TOTAL DEPTH: 4516'  
PIPE: 1/2" @ 4516'  
SURFACE CASING: 8 5/8" @ 265'

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: SHAWNEE WELL SERVICE

ADDRESS: ATTICA, KS LICENSE: 30346

COMPANY TO PLUG AT: HOUR: DAY: MONTH: YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: JEFF CAPPS

COMPANY NAME: SHAWNEE WELL SERVICE PHONE:

WERE: PERFS: 4508-12'  
SAND TO 4400' AND 4 SACKS  
35 SACKS AT 1350'  
35 SACKS AT 900'  
CIRCULATE 300' TO SURFACE

PLUGGING PROPOSAL RECEIVED BY:

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( ) PART ( X ) NONE ( )

COMPLETED: HOUR: 17:30 DAY: 19 MONTH: 9 YEAR: 1997

ACTUAL PLUGGING REPORT: A CIBP WAS SET AT 4400' AND CAPPED WITH 2 SACKS OF CEMENT.  
CASING WAS RECOVERED FROM 3702' AND PULLED TO 1354' WHERE 35 SACKS OF CEMENT  
WAS SPOTTED. CASING PULLED TO 924' WHERE 35 SACKS OF CEMENT WAS SPOTTED.  
CASING WAS PULLED TO 324' WHERE CEMENT WAS CIRCULATED TO SURFACE.

REMARKS: 60/40 POZ 4% GEL ALLIED CEMENT

RECEIVED  
KANSAS CORPORATION COMMISSION

I DID OBSERVE THIS PLUGGING.

*[Signature]*  
STEVE VAN GIESON

INVOICED

NOV 06 1997

DATE NOV 07 1997

CONSERVATION DIVISION  
WICHITA, KS

INV. NO. 49458