

15-007-19078-00-00

342

To: 1 051575
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drilled 11/24/63

SE NW SW, SEC. 26, T. 32 S, R. 13 W/E
1650 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5435

Lease Name Binning Well # 1
County Barber 127.72

Operator: Bowers Drilling Company, Inc.
Name & Address P.O. Box 241
Medicine Lodge, KS 67104

Well Total Depth 3930 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 280

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635
Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 12 p.m. Day: 3 Month: 9 Year: 19 92

Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 3930' with 175 sx cement, PBSD 3850', Perfs at 3569-76'
1st plug sand back to 50' above perfs and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:45 p.m. Day: 3 Month: 9 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 3520' and dumped 4 sx cement on top of sand through bailer.

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.
Maximum pressure 900 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmxi 6% gel by Allied. Recovered 2415.35' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I do hereby certify to serve this plugging.

DATE 10-2-92
INV. NO. 36299

Signed Richard W. Lacey (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
SEP 8 1992
CONSERVATION DIVISION
Wichita, Kansas