

1080226

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,267-00-00

E/2 NE SE, SEC. 24, T 32 S, R 13 W/2X
1980 feet from N/2X SE Corner of
990 feet from W/2X SE Corner of

TECHNICIAN'S PLUGGING REPORT

Operator License # 5428

Lease Name Lonker Well # 1

Operator: Graves Drilling Co., Inc.

County Barber

Name & Address 910 Union Center

Well Total Depth 4477 145.50 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 208

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, K S 67104

Company to plug at: Hour: 1:00 pm Day: 1 Month: October Year: 19 84

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 4 1/2" set at 4476' Perfs at 4416-28' PBDT 4451'

1st plug sand back to 4375 and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel and 100

sx cement

Plugging Proposal Received by J. H. Metz (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:45 pm Day: 1 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4476' Perfs at 4416-28' PBDT 4451'

1st plug sanded back to 4375' and dumped 4 sx cement on top of sand through bailer

2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel and 100

sx cement

Maximum pressure 800 psi and shut in pressure 500 psi

RECEIVED STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Buie

(if additional description is necessary, use BACK of this form.)

OCT 05 1984 10-5-84

Observe this plugging.

DATE 10-8-84

Signed J. A. Metz (TECHNICIAN) SLD

INV. NO. 4131

10-1