

1 060557

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,467-00-00

SE NE, SEC. 24, T 32 S, R 13 W/E

3300 feet from S section line

480 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Lonker "E" Well # 1

Operator: TXO Production Corp.

County Barber 147.23

Name & Address 200 West Douglas, Suite 300

Well Total Depth 4530 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 257.68

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:00 am Day: 9 Month: May Year: 19 85

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 4 1/2" at 4529' PBD 4519' Perfs at 4408-20'

1st plug sand back to 4360' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

and 150 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:00 am Day: 9 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4360' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 150 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 12 1985
5-13-85

CONSERVATION DIVISION

Maximum pressure 750 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by B.J.-Titan. Recovered 3500 Wichita, Kansas casing.

(If additional description is necessary, use BACK of this form.)

I (did did not) observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

INVOICED

DATE 5-14-85

INV. NO. 8141