

1 010087

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,392 -00-00

SE NE NE, SEC. 24, 'T 32 S, R 13 W/E  
4290 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5428

Lease Name Lonker Well # 2  
County Barber 144.92

Operator: Graves Drilling Co., Inc.  
Name & Address 910 Union Center  
Wichita, KS 67202

Well Total Depth 4459 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 211

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address P. O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:25 am Day: 7 Month: February Year: 19 86

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 4 1/2" at 4458' PBTD 4440' Perfs at 4368-74'; 4392-98'

1st plug sand back to 4318' and dump 4 sx cement on top of sand through bailer  
2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,  
release 8 5/8" rubber plug and pump 110 sx cement.

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:15 am Day: 7 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4318' and dumped 5 sx cement on top of  
sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10  
sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 110 sx cement.

Maximum pressure 900 psi and shut in 400 psi

Remarks: Recovered 3050' 4 1/2" casing. Used 60/40 Pozmix 2% cc by BJ-Titan  
(If additional description is necessary, use BACK of CONSERVATION DIVISION  
Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

FEB 17 1986

INVOICED  
( ) observe this plugging.

Signed Jack [Signature]  
(TECHNICIAN)

DATE 1-17-86

INV. NO. 12617