

1080160

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,460-00-00

NE SW NE, SEC. 24, T 32 S, R 13 W/E

feet from N/S section line

feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5425

Lease Name Lonker Well # 3

Operator: Graves Drilling Co.  
Name & Address: 910 Union Center  
Wichita, KS 67202

County Barber  
Well Total Depth 4450 144.63 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 230

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:30 am Day: 7 Month: June Year: 19 84

Plugging proposal received from Elmo Morgernstern

(company name) Clarke (phone) 316-886-5665

were: 4 1/2 set at 4480 PBD 4439 Perf 4374-78

1st plug sand back to 4325 and dump 4 sx cement on top of sand

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 100 sx cement.

Plugging Proposal Received by *J. A. King* (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11:30 am Day: 7 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 4480' PBD 4439' Perf 4374-78'

1st plug sanded back to 4325' and dumped 4 sx cement on top of sand through bailer,

2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 100 sx cement.

Maximum pressure 300# and shut in pressure 250#.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Buie. They recovered 2800' of 4 1/2" casing.

RECEIVED (If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION (City of Wichita) observer at plugging.

JUN 14 1984

INVOICED

Signed *J. A. King* (TECHNICIAN)

CONSERVATION DIVISION  
Wichita, Kansas

DATE 6-18-84  
INV. NO. 2061 6-7