

1 040378

12-14 15-007-21058-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 9/11/81

C NW/4, SEC. 35, T 33 S, R 13 W/E

3960 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992

Lease Name Holmes Well # Q-1

Operator: Patton Oil Company

County Barber 158.93

Name & Address

672 West 4th

Well Total Depth 4890 feet

Hoisington, KS 67544

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 205

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10 a.m. Day: 14 Month: 12 Year: 19 89

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4746' PRTD 4686' Perfs at 4610-22'

1st plug sand back to 4560' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:30 a.m. Day: 14 Month: 12 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4560' and dumped 4 sx cement on top of sand bridge with bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 300 psi and shut in 120 psi.

Remarks: Used 60/40 Pozmix 2% gel 2% cc by B.J. Titan. Recovered 3400' of cement.
(If additional description is necessary, use BACK of this form.)

STATE RECEIVED
12-19-89
CONSERVATION DIVISION
Wichita, Kansas

INVOICED observe this plugging.

Signed Stephen J. Pfeiffer (TECHNICIAN)

DATE 1-3-1990

INV. NO. 20868