

State of Kansas



JOHN ANDERSON, Jr. Governor  
 WILLIAM L. MITCHELL Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 ROBT. C. LONDERHOLM Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN 4 1965  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Webb Hill of Mack Oil Company has this  
 date requested permission to plug the following described well:

Mr. Hill guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Company

Complete Address: 812 Union Center, Wichita, Kansas

Lease Name: McKenny Well No. # 1

Location: C SW SW Sec. 16 Twp. 33 Rge. 8 (E) (W) W

County Harper Total Depth 4993 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Hill was instructed to plug the well as follows:

249' of 8 5/8" surface pipe, cement circulated with 175 sacks.  
Fill hole with drilling mud to 240', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drilling  
mud to 40', 2nd cementing plug, bridge with hulls, and cement  
with 10 sacks to base cellar. Bridge and cement rat hole with  
2 sacks.

Very truly yours,

Archie Elving