

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

DEC 8 1966

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Red Bishop of Leben Drilling, Inc. has this
 date requested permission to plug the following described well:

Mr. Bishop guarantees payment of the plugging fee.

Operator's full Name: W. C. Pickens

Complete Address: 2000 Fidelity Union Tower, Dallas, Texas

Lease Name: Hayes Well No. # 1

Location: C NW NE Sec. 30 Twp. 33 Rge. 8 (E)(W)W

County Harper Total Depth 4937' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bishop was instructed to plug the well as follows:

280' of 8 5/8" surface pipe, cement circulated with 210 sacks. Fill
 hole with drilling mud to 260', 1st cementing plug, bridge with 1/2 sack
 of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent