



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 12 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sweetman of Sweetman Drlg Co has this
date requested permission to plug the following described well:

Mr. Sweetman guarantees payment of the plugging fee.

Operator's full Name: McCoy Petroleum & Petroleum Inc

Complete Address: 502 Union Center Wichita, KS

Lease Name: Kastens A Well No. 2

Location: G S/2 SW Sec. 28 Twp. 33 Rge. 8 (E)(W) W

County: Harper Total Depth 4725 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sweetman was instructed to plug the well as follows:

260 ft 8 5/8 surface cemented with 200 sacks. Fill hole

to 250 ft, plug, 1/2 sack hulls, 35 sacks cement. Mud to

40 ft, plug, 1/2 sack hulls, 10 sacks cement to surface.

2 sacks cement in rat hole.

Very truly yours,

G. Russell Bickert
Conservation Division Agent