

State of Kansas



FORM CP-2

15-077-20322-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

1506 DIS
8-6-75

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sweetman of Sweetman Drlg has this
date requested permission to plug the following described well:

Mr. Sweetman guarantees payment of the plugging fee.

Operator's full Name: Robinson Oil Co & Sweetman Drlg Co

Complete Address: 340 R.H. Garvey Bldg Wichita, KS

Lease Name: Heath Gas Unit Well No. 1

Location: C W/2 NE Sec. 28 Twp. 33 Rge. 8 (E)(W) W

County: Harper Total Depth 4690 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sweetman was instructed to plug the well as follows:

266 ft 8 5/8 surface cemented with 200 sacks. Fill hole
to 250 ft, plug, 1/2 sack hulls, 25 sacks cement. Mud to
40 ft, plug, 1/2 sack hulls, 10 sacks cement to surface.
2 sacks cement in rat hole.

Very truly yours,