

State of Kansas



15-077-20385-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSIONOCT 26 1976
10-26-76
CONSERVATION DIVISION
WICHITA, KANSASJ. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. French of Pickrell Drlg Co has this
date requested permission to plug the following described well:Mr. French guarantees payment of the plugging fee.Operator's full Name: Pickrell Drlg CoComplete Address: 205 Litwin Bldg Wichita, KSLease Name: Norman-Dalrymple B Unit Well No. 1Location: NE/SW Sec. 25 Twp. 33s Rge. 8 (E)(W) WCounty: Harper Total Depth 4710 Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. French was instructed to plug the well as follows:210 ft 8 5/8 surface cemented with 185 sacks. Pump plug,
35 sacks cement to 200 ft. Mud to 40 ft, plug, 1/2 sack
hulls, 15 sacks cement to surface. 5 sacks cement in
rat hole.

Pumped by Allied Cementing Great Bend, KS

Very truly yours,

Conservation Division Agent