

State of Kansas



FORM - CP-2

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSASVERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)RECEIVED  
STATE CORPORATION COMMISSION

MAR 19 1964

CONSERVATION DIVISION  
Wichita, KansasJ. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Bill Musgrove of Bowers Drilling Co. has this

date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.Operator's full Name: Bowers Drilling Co.Complete Address: 416 Union Center Bldg., Wichita, KansasLease Name: Lonker "E" Well No. # 1Location: C S/2 NW SE Sec. 26 Twp. 32 Rge. 13 (E) (W) WCounty Barber Total Depth 4482 Oil Well Gas Well  Input Well  SWD Well  D & A X Lost Hole Mr. Musgrove was instructed to plug the well as follows:

319' of 8 5/8" surface pipe, cemented with 225 sacks. Fill  
hole with drilling mud to 300', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drill-  
ing mud to 40', 2nd cementing plug, bridge with hulls and  
cement with 10 sacks to base cellar. Bridge and cement rat  
hole with 2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent