



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
ALVIN P. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

JUN 14 1965

6-14-65
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bill Musgrove of Bowers Drilling Company has this date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: Bowers Drilling Company

Complete Address: 1434 Wichita Plaza, Wichita, Kansas

Lease Name: Watkins Well No. # 1

Location: C NE NE Sec. 20 Twp. 31 Rge. 11 (E) (W) W

County Barber Total Depth 4500' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Musgrove was instructed to plug the well as follows:

360' of 8 5/8" surface pipe, cement circulated with 275 sacks.

Fill hole with drilling mud to 340', 1st cementing plug, bridge with hulls, and cemented with 25 sacks. Fill hole with drilling

mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent