

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1963
9-23-63

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Amerada Petroleum Corporation

Complete Address: Box 197, Great Bend, Kansas

Lease Name Edd Sterling Well No. # 1

Location C NW NW Sec. 35 Twp. 34 Rge. 13 (E) (W) W

County Barber Total Depth 3608

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractors: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 12:00PM Day 21st Month Sept. Year 1963

The Above well was plugged as follows:

298' of 8 5/8" surface pipe, cemented to top. 3608' of 5 1/2" long string,
cemented with 150 sacks. Top perferation 3595'. Bottom of hole was sand-
ed to 3580', cemented with 5 sacks through dump bailer. Fluid level was
up in hole. Plug was pushed to 275', 10' rock bridge. 5 sacks cement was
mixed in barrel and put on plug through dump bailer, and let set over
night. Next morning hole bailed down and 16 sacks cement was added to
plug. Hole was filled with mud to 40', 10' rock bridge, cemented with 10
sacks to base cellar. 2810' of 5 1/2" long string was recovered from hole.

I hereby certify that the above well was plugged as herein stated.

DATE

9/23/63

INV. NO.

7773-W

Signed:

Arlene Elving
Well Plugging Supervisor