

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 129-10 County: Barber

Location: SE SE SE Sec. 27 Twp. 34 Rge. 13 (E) (W) X

Name of Field: _____ Total Depth: 3700

I have this date completed supervision of plugging of:

Lease Name: Sterling Well No. 1

Operator's Full Name: Magnolia Petroleum Co.

Complete Address: Box 770, Great Bend, Kans.

Plugging Contractor: R & D Casing Pulling Co.

Address: Ellenwood, Kans. License No. 239

Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No X

If yes how long? _____ Reason: _____

Operation Completed: Hour 4 PM Day 31 Month Oct. Year 1958

The above well was plugged as follows:

345' of 8 5/8" surface casing circulated with cement. Oil String set at
3699'. Top Perf 3616 to 3626'. Bottom cemented off with 50 sack cement by
Halliburton Cementing Co. Pipe was pulled and hole filled to 345' with
heavy mud. A rock bridge set from 345' with 20 sack cement placed top
bridge. Heavy mud to 40' with rock bridge set from 40'. 10 sack cement
placed from bridge to nose of cellar.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

NOV 12 1958
11-12-58
CONSERVATION DIVISION
Wichita, Kansas
[Signature]

PLUGGING
FILE SEC. 27 T. 34 R. 13W
BOOK PAGE 129 LINE 10