

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 9 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Barbara Oil Co.

Complete Address 509 Union Center Wichita, Ks

Lease Name Wilson Estate Well No. 1

Location C SE/4 Sec. 17 Twp. 33 Rge. 13 (E) (W) W

County Barber Total Depth 5189

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Clarke Oilfield Service

Address 107 W. Toliver Medicine Lodge, Ks License No. 583

Operation Completed: Hour 10:00 AM Day 7 Month 9 Year 1971

The above well was plugged as follows:

274 ft 10 3/4 surface pipe cemented with 260 sacks. 5189 ft 7" long  
string cemented with 250 sacks. Top perf. at 4076 ft. Sand back  
to 4060 ft. 7 sacks cement with bailer. Pulled 2700 ft 7". Set  
20 ft rock bridge at 250 ft. Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 9-10-71

INV. NO. 4304-W