

15-007-30223-0000

Form CP-3  
Rev. 6-26-62

**KANSAS**  
**STATE CORPORATION COMMISSION**  
**CONSERVATION DIVISION AGENT'S REPORT**

**RECEIVED**  
STATE CORPORATION COMMISSION

JAN 3 1966

1-3-66  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Sioux Petroleum

Complete Address: Medicine Lodge, Kansas

Lease Name Shepherd Well No. # 3

Location C NE SE Sec. 24 Twp. 31 Rge. 11 (E) (W) W

County Barber Total Depth 4570'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Leben Drilling, Inc.

Address: 815 Wichita Plaza, Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 12:00AM Day 28th Month Dec. Year 1965

The Above well was plugged as follows:

212' of 8 5/8" surface pipe, cement circulated with 200 sacks. Hole was filled with drilling mud to 200', 1st cementing plug, bridged solid with dry cement and hulls on fluid at 200', and cemented with 25 sacks.  
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged solid with dry cement and hulls on fluid at 40', and cemented with 10 sacks to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Archie Elving  
Well Plugging Supervisor

DATE 1/4/66  
INV. NO. 2532-U