

15-077-20026-00-00

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
OIL & GAS CORPORATION COMMISSION
NOV 3 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed October 17, 1967.

Dear Sir:

Mr. Otto Beren of Donelson Drilling Co. has this
date requested permission to plug the following described well:

Mr. Beren guarantees payment of the plugging fee.

Operator's full Name: Deck Oil Company

Complete Address: 2702 Fourth National Bank Bldg., Tulsa, Oklahoma 74100

Lease Name: Rife Well No. # 1

Location: NE NW SW Sec. 30 Twp. 34 Rge. 6 (E)(W) W

County Harper Total Depth 5265' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Beren was instructed to plug the well as follows:

240' of 8 5/8" surface pipe, cement circulated with 175 sacks. Fill
hole with drilling mud to 225', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent