

State of Kansas



WM. H. AVERY Governor  
 WILLIAM L. MITCHELL Chairman  
 JAMES O. GREENLEAF Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg.  
 WICHITA, KANSAS 67202

RECEIVED  
 STATE CORPORATION COMMISSION

NOV 14 1966

CONSERVATION DIVISION  
 Wichita, Kansas

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita 2, Kansas

Dear Sir:

Mr. Jack Gabbert of Gabbert-Jones, Inc. has this date requested permission to plug the following described well:

Mr. Gabbert guarantees payment of the plugging fee.

Operator's full Name: Ben F. Taylor

Complete Address: 2809 Northwest Expressway, Oklahoma City, Ok.

Lease Name: Denton Well No. # 1

Location: App. C SW NE Sec. 30 Twp. 34 Rge. 6 (E)(W) W

County Harper Total Depth 5230' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Gabbert was instructed to plug the well as follows:

297' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fill hole with drilling mud to 280', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of the cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

*Audie Elving*

Conservation Division Agent