

15-077-20009-00-00

State of Kansas



WM. H. AVERY Governor
WILLIAM E. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 17 1967
3-17-67

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed March 28, 1967.

Dear Sir:

Mr. Bob Canady of Corbett Drilling Company has this
date requested permission to plug the following described well:

Mr. Canady guarantees payment of the plugging fee.

Operator's full Name: J. R. Butler

Complete Address: 2138 Bank of Southwest Bldg., Houston, Texas

Lease Name: Charlie Carr Well No. # 1

Location: C NW NW Sec. 23 Twp. 34 Rge. 7 (E)(W) W

County Harper Total Depth 5155' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Canady was instructed to plug the well as follows:

262' of 8 5/8" surface pipe, cement circulated with 175 sacks. Fill
hole with drilling mud to 250', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat & mouse holes with 5 sacks

Very truly yours,

Archie Elving
Conservation Division Agent