

State of Kansas



15-007-30225-0000

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
3-27-68  
MAR 27 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Morganstern of Sioux Petro. Co. has this

date requested permission to plug the following described well:

Mr. Morganstern guarantees payment of the plugging fee.

Operator's full Name: Sioux Petroleum Co.

Complete Address: Box 117, Medicine Lodge, Kansas

Lease Name: Stephenson Well No. 1

Location: C NW NW Sec. 27 Twp. 31 Rge. 11 (E) (W)

County Barber Total Depth 3763' Oil Well         

Gas Well X Input Well          SWD Well          D & A X Lost Hole         

Mr. Morganstern was instructed to plug the well as follows:

8 5/8" to 290' circulated w/ cement. 4 1/2" to 3754' cemented.

No perforations Plug bottom w/ sand & 5 sacks cement.

Top of cement 3700' Mud 3700' to 290'

Rock Bridge & 25 sacks cement 290' to 190' Mud 190' to 40'

Rock Bridge & 10 sacks cement 40' to 0'.

Very truly yours,

  
Conservation Division Agent