



*CPJ*

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

6-15-70  
JUN 15 1970

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Howard of Sage Drlg. Co. Inc. has this date requested permission to plug the following described well:

Mr. Howard guarantees payment of the plugging fee.

Operator's full Name: Beason Resources Corp.

Complete Address: 1000 Century Plaza Wichita, Ks

Lease Name: Stephenson Well No. 1

Location: <sup>NW</sup>~~NE~~/NE/SW Sec. 27-Twp. 31s Rge. 11 (E)(W) W

County: Barber Total Depth 4560 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Howard was instructed to plug the well as follows:

251 ft of 8 5/8 surface pipe cemented with 250 sacks. Fill  
hole to 240 ft, plug, 1/2 sack hulls, 25 sacks cement. Mud  
to 40 ft, plug, 1/2 sack hulls, 10 sacks cement to surface.  
2 sacks cement in rat hole.

Very truly yours,

*M. Russell Baker*  
Conservation Division Agent