

State of Kansas



FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUENHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Building
212 North Market
Wichita, Kansas
RECEIVED
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

JUL 1 1963
7-1-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Buck Hall of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Hall guarantees payment of the plugging fee.

Operator's full Name: Aylward Drilling Co.

Complete Address: 909 1st National Bank Bldg., Wichita Kans.

Lease Name: Nuckolls "A" Well No. # 1

Location: NE NE SW Sec. 30 Twp. 31 Rge. 11 (E) (W) W

County Barber Total Depth 4297 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hall was instructed to plug the well as follows:

124' of 12½" surface pipe, cement circulated, 4277' of
7" long string, cemented with 125 sacks, Sand to 4260',
cement with 6 sacks. Fill hole with mud to 200', 10' rock
bridge, cement with 30 sacks. Fill hole with mud to 40',
10' rock bridge, cement with 20 sacks to base cellar.

Very truly yours,

Archie Elving
Conservation Division Agent